

□
Clichy riverbanks
Clichy
2010

Description technique des travaux

Localized protection and safety works on the riverbanks of Clichy. Supply and installation of metal piles. Demolition in and out of water, excavation out of water, dredging including evacuation, supply and installation of riprap in water. Supply and installation of riprap out of water. Prefabrication and installation of reinforced concrete elements. Reinforced concrete structures poured on site.

Rubblework.

Maître d'Ouvrage

CG 92

Maître d'Œuvre

CG 92

Montant des travaux H.T

1 490 000

Enjeux / Valeur ajoutée

Métier du groupe

- Travaux maritimes et fluviaux - Travaux sous-marins

Savoir Faire

- Improvement and development of embankments

Le chantier en chiffres

- **200 m³ of stonework**
 - **48 x 13-m piles**
 - **200 tonnes of riprap**
 - **200 m**
-