

□
Clichy riverbanks
Clichy
2010

Description technique des travaux
Localized protection and safety works on the riverbanks of Clichy. Supply and installation of metal piles. Demolition in and out of water, excavation out of water, dredging including evacuation, supply and installation of riprap in water. Supply and installation of riprap out of water. Prefabrication and installation of reinforced concrete elements. Reinforced concrete structures poured on site. Rubblework.
Maître d'Ouvrage
CG 92
Maître d'Œuvre
CG 92
Montant des travaux H.T
1 490 000
Enjeux / Valeur ajoutée
Métier du groupe
• Travaux maritimes et fluviaux - Travaux sous-marins
Savoir Faire

- Improvement and development of embankments

Le chantier en chiffres

- 200 m3 of stonework
- 48 x 13-m piles
- 200 tonnes of riprap
- 200 m