

□
Anse Saint Marc 2 quay
LA ROCHELLE
2014

Description technique des travaux
Quay on piles with 2 dolphins (docking and mooring), north side of quay. This structure will serve to receive a bulk carrier type ship. The quay consists of a system of beams and a reinforced concrete deck, connected by headpieces to metal piles, all filled with concrete and anchored in the bedrock.
Maître d'Ouvrage
GRAND PORT MARITIME DE LA ROCHELLE
Maître d'Œuvre
GRAND PORT MARITIME DE LA ROCHELLE
Montant des travaux H.T
21 348 367
Enjeux / Valeur ajoutée
Métier du groupe
• Travaux maritimes et fluviaux - Travaux sous-marins
Savoir Faire

•

Le chantier en chiffres

- **Length: 200 m**
- **2445 tonnes of tubes**
- **1750 tonnes of reinforcement**
- **11,868 m3 of concrete**