

□
Anse Saint Marc 2 quay
LA ROCHELLE
2014

Description technique des travaux

Quay on piles with 2 dolphins (docking and mooring), north side of quay. This structure will serve to receive a bulk carrier type ship. The quay consists of a system of beams and a reinforced concrete deck, connected by headpieces to metal piles, all filled with concrete and anchored in the bedrock.

Maître d'Ouvrage

GRAND PORT MARITIME DE LA ROCHELLE

Maître d'Œuvre

GRAND PORT MARITIME DE LA ROCHELLE

Montant des travaux H.T

21 348 367

Enjeux / Valeur ajoutée

Métier du groupe

- Travaux maritimes et fluviaux - Travaux sous-marins

Savoir Faire

•

Le chantier en chiffres

- **Length: 200 m**
 - **2445 tonnes of tubes**
 - **1750 tonnes of reinforcement**
 - **11,868 m³ of concrete**
-