

□
ACM2S mooring Dolphin
La Rochelle
2016

Description technique des travaux

Total replacement of the west oil terminal pier mooring dolphin. Installation of a guide tube, procurement and installation of the dolphin by flotation and ballasting, embedding of tube base in bore, installation and embedding of the cap with the tube, reinforcement and concreting of the tube head, installation of mooring hook and removal of damaged dolphin after cut off.

Maître d'Ouvrage

GRAND PORT MARITIME DE LA ROCHELLE

Maître d'Œuvre

GRAND PORT MARITIME DE LA ROCHELLE

Montant des travaux H.T

2 300 000

Enjeux / Valeur ajoutée

Métier du groupe

- Travaux maritimes et fluviaux - Travaux sous-marins

Savoir Faire

-

Le chantier en chiffres

- **Dolphin length: 32.70 m - Weight: 64 tonnes**
 - **250 tonnes: installation of mooring hook**
-
-